

**THE NAVAJO NATION
FACILITIES MAINTENANCE DEPARTMENT
REQUEST FOR PROPOSALS (RFP)
AMENDMENT NO. 1**

**RFP # 21-12-2680LE
ADA RAMPS
AND
CONCRETE PARKING PADS INSTALLATION
NAVAJO NATION
Re-ADVERTISEMENT
GENERAL INSTRUCTIONS
DUE: April 15, 2022 4:00 P.M.**

The Navajo Nation Facilities Maintenance Department (here after referred to as FMD) issues the following Amendment Number One to RFP # 21-12-2680LE as follows:

1. SCOPE of WORK:

Pinon WIC Building:

- Add 4" rain gutter with down spout and splash block over ramp. Color should match exterior building color.

General Specifications:

- All walk ways are 4" in thickness.
- All concrete parking pads dimensions are 8' x 15' x 20'. No. 5 rebar on 24" on center as reinforcement.
- All metal ramps materials are: 1 ½" square mesh wire, 2" OD round pipe, 2 ½" angel iron.

2. TIME FRAME WILL NOT CHANGE.

3. ALL OTHER RFP REQUIREMENTS NOT SPECIFICALLY CHANGED HEREIN SHALL REMAIN AS ORIGINALLY ISSUED.